Certain depots in or adjoining the forests will, however, be set apart and remain open throughout the whole of this period for the removal of timber for the convenience of those purchasers who may choose to collect timber therein in order to avoid the inconvenience of an interruption of their transport operations during the fire season.

6. The rates and conditions of sale are regulated by Notification No. 53, dated 7th September 1903, of the Chief Commissioner of Coorg, for copy of which or further information apply to the undersigned.

Note.—Any tenders made after 10th September 1907, will be subject to a late fee of 1 anna per rupee of value of tender.

MERCARA,
Dated 3rd August 1907.

C. MCCARTHY,
Dy. Consvr. of Forests, Coorg.

TUMKUR DIVISION.

Dated 28th August 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 21st September 1907, for restoring Teriyur tank, Registered No. 168, Maddagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for Teriyur tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign a ny reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work	*Per*	*Quantity.*
Bund at R. L. 55·00.		
Earthwork to bund, including watering and tamping	C. yd.	25,616
Picking to the seat of new bund, 9"	S. yds.	916
Cutting trench in the new bund and using the earth to bund	C. yd.	55
Stone pitching 9" new bund	do	101
Turfing to bund	S. yd.	17,516
Grade stone with bed slab and index stones chiselled, including painting numbering and fixing complete	No.	54
B. M. stone do	No.	2
Register number stone do	do	1
Date stone do	do	1
Gauge stone as per circular orders do	do	1
Sluice No. I.		
Earthwork, cutting old bund and refilling, with consolidation	C. yd.	71
Burnt brick in surki mortar	C. ft.	917
Removing and fixing old slabs after dressing	S. ft.	274
Plastering with surki mortar	Sqr.	8·78
Chain and plug to orifices	Lump sum	No. 1
Gibbet stone cutting and fixing to suit the present design	Lump sum.	
Blocking up the old sluice	Do	

Description of work.	*Per*	*Quantity.*
Sluice No. II.		
Details as per No. 1 sluice and add lump sum for the gibbets and orifices, etc.	Lump sum.	
Right waste-weir, 80' long.		
Earthwork, excavation for foundation and using the earth to bund ...	C. yd.	89
Burnt brick in surki mortar	C. ft.	374
Burnt stone slabs, two faces, dressed	S. ft.	345
Rough stone for apron with 6" jelly packing	C. yd.	84
Plastering with surki mortar	Sqr.	1·00
Feeder.		
Blocking old breach to divert the water between C. S. 10 to C. S. 15 of the feeder halla	.....	
Earthwork to breach with consolidation	C. yd.	1,204
Cutting trench in centre of breach and using it to bund with consolidation ...	do	48
Rough stone revetment, stone available within 2 furlongs	do	47
Turfing	S. yd.	303

C. A. MAHADEVASASTRI,
Executive Engineer.

SHIMOGA DIVISION.

Dated 31st August 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 23rd September 1907, for constructing dispensary with out-houses at Kumsi. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. Rates tendered should include royalty on stones, etc., removed from the Government lands.

4. Each tender must be accompanied by a deposit of Rupees two hundred only in Government currency notes, as earnest money, and be superscribed "Tender for constructing Dispensary with Out-houses at Kumsi," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	*Description of work.*	*Per*	*Quantity.*
1	Clearing site and levelling ground	Lump sum.	
2	Earthwork excavation	C. yd.	137
3	Do filling	Do	81
4	Burnt stone in lime mortar, foundation and basement ...	C. ft.	4,947
5	Burnt stone in lime mortar, superstructure	Do	7,863
6	Burnt stone in lime mortar, archwork	Do	84
7	Burnt stone slabs dressed and fixed	S. ft	634
8	Lime mortar plastering to stone walls, interior	Squrs.	56·43
9	Lime mortar pointing to stone walls, exterior	Do	56·43
10	White and color washing	Do	113·13
11	Flooring with 1st class 9" square Mangalore tiles on 3" concrete bed, and cement pointing	Do	17·10